



SSOP36 EVALUATION (STAGE @ Trim and Form)				
Evaluation Done after Trim and Form Process (Temp: 18~27 degC, RH: 35~55%)				
EXPOSURE TIME	BENDING (w/ forming process)		NO BEND (w/out forming Process)	
	Solderability Test	Visual Inspection	Solderability Test	Visual Inspection
No Staging (Control)	PASS	No Discolor	PASS	No Discolor
4 days	PASS	No Discolor	PASS	No Discolor
7 days	PASS	No Discolor	0/10	No Discolor
2 weeks	FAIL - 4/10	With discoloration	FAIL - 3/10	With discoloration
Extra High - 1 month	FAIL - 1/10	With discoloration	FAIL - 6/10	With discoloration
Note: Final Test cycle time is 7 days.				

Electrical Characteristic Summary:

There are no changes in electrical performance. Datasheet specifications are not affected by this change.

List of affected Standard Parts:

- NCV7471DQ5R2G
- NCV70522DQ004R2G
- NCV70627DQ001R2G
- NCV7462DQ0R2G
- NCV7608DQR2G
- NCV78663DQ0R2G
- NCV78763DQ0R2G